

SUNON

SPECIFICATION FOR APPROVAL

CUSTOMER :
DESCRIPTION : DC BRUSHLESS FAN
DIMENSIONS : 40X40X56 mm
MODEL : PMD1204PPB1-A
P/N : (2).GN
SUNON SPEC. NO. : D04041840G-00
APPROVAL NO. :
APPROVED BY :

(AUTHORIZED)

DRAWN	Apple 6/29	CHECKED	<i>M. M. 6/29</i>	APPROVED	<i>[Signature]</i>	SPEC.NO	D04041840G-00
						ISSUE DATE	06.02.2005
						EDITION	1
						REVISION DATE	06.29.2005
						E.SPEC	EN40016

建準電機工業股份有限公司

SUNONWEALTH ELECTRIC MACHINE INDUSTRY CO., LTD.

12FL., 120 CHUNG CHENG 1ST RD.,

TEL:886-7-71630611(41 LINES)

KAOHSIUNG, TAIWAN, R. O. C.

FAX:886-7-7163086~811



DC BRUSHLESS FAN
MODEL : PMD1204PPB1-A
P/N : (2).GN

CHARACTERISTICS

- 1. Motor Design** : DC brushless 4 pole motor design.
- 2. Insulation Resistance** : More than 10M ohm between internal stator and lead wire(+) measured at DC 500V.
- 3. Dielectric Strength** : Applied AC 500V for one minute or AC 600V for 2 seconds between housing and lead wire(+)
- 4. Noise Level** : Measured in a semi-anechoic chamber with background noise level below 15 dB(A). The fan is running in free air with the microphone at a distance of one meter from the fan intake.
- 5. Input Power, Current & Speed** : Measured after continuous 10 minute operation at rated voltage in clean air, and at ambient temperature of 25 degrees C.
- 6. Tolerance** : $\pm 15\%$ on rated power and current.
- 7. Air Performance** : Measured by a double chamber. The values are recorded when the fan speed has stabilized at rated voltage.

建準電機工業股份有限公司
 SUNONWEALTH ELECTRIC
 MACHINE INDUSTRY CO., LTD.

SPEC.NO	D04041840G-00	REVISION DATE	06. 29. 2005
ISSUE DATE	06. 02. 2005	E D I T I O N	研發部
P A G E	2 O F 9		94.07.11



SPECIFICATIONS

MODEL: PMD1204PPB1-A

P/N : (2).GN


	4056	4024	4024
1-1. Rated Voltage	: 12 VDC		
1-2. Operating Voltage Range	: 6~13.8 VDC		
1-3. Starting Voltage	: 6 VDC (25 deg. C POWER ON/OFF)		
1-4. Rated Speed (± 10 %)	: 14500 / 9500 RPM	14500 RPM	12000 RPM
1-5. Air Delivery	: 26.5 CFM	23.5 CFM	20.0 CFM
1-6. Static Pressure	: 1.73 Inch-H ₂ O	1.26 Inch-H ₂ O	0.90 Inch-H ₂ O
1-7. Rated Current	: 1.40 AMP	0.78 AMP	0.45 AMP
1-8. Rated Power	: 16.8 WATTS	9.4WATTS	5.4 WATTS
1-9. Noise Level	: 59 dB(A)	55 dB(A)	49 dB(A)
1-10. Direction of Rotation	: Clockwise & Counter-clockwise	Counter- clockwise	Clockwise
	Viewed from front of fan blade		
1-11. Operating Temperature	: -10 to +70 deg. C		
1-12. Storage Temperature	: -40 to +70 deg. C		
1-13. Bearing System	: Precision ball bearing system		
1-14. Weight	: 88.4 g	41.6 g	41.6 g
1-15. Safety	: UL/CUR/TUV/CE Approvals		
1-16. Vibration	: Vibration of acceleration 1.5G and frequency 5~50~5Hz is applied in all 3 directions(X,Y,Z), in cycles of 1 minute each, for a total vibration time of 30 minutes.		
1-17. Locked Rotor Protection	: Automatic Restart Capability Note: In a situation where the fan is locked by an external force while the electricity is on, an increase in coil temperature will be prevented by temporarily turning off the electrical power to the motor. The fan will automatically restart when the locked rotor condition is released.		



MODEL : PMD1204PPB1-A

P/N : (2).GN

PERFORMANCE CURVES



建準電機工業股份有限公司
 SUNONWEALTH ELECTRIC
 MACHINE INDUSTRY CO., LTD.

SPEC.NO	D04041840G-00	REVISION DATE	06.29.2005
ISSUE DATE	06.02.2005	EDIT I O N	研發部
P A G E	4 OF 9		94.07.11


REVISION DATE 06.29.2005
 EDIT I O N 研發部
 94.07.11

發行章

MATERIAL

- 2-1. Frame : Thermoplastic PBT of UL 114V-0
- 2-2. Impeller : Thermoplastic PBT of UL 114V-0
- 2-3. Bobbin : Thermoplastic PBT of UL 114V-0
- 2-4. Lead Wire : UL1571,28 awg,+RED, -BLACK

DIMENSIONS



1. Air Flow Direction: Toward label side.
2. Best Mounting Direction: Any orientation.

UNITS: mm

建準電機工業股份有限公司
SUNONWEALTH ELECTRIC
MACHINE INDUSTRY CO., LTD.

SPEC.NO	D04041840G-00	REVISION DATE	06.29.2005
ISSUE DATE	06.02.2005	E D I T I O N	
P A G E	5 OF 9		



Notes

I . Safety

- 1.SUNON will not guarantee this product if your application exceeds the limitations outlined in this specification.**
- 2.There is no thermo-protector installed in this product, such as thermo-fuse, or current-fuse or thermo-protector. There may be smoking, ignition, or electric shock by insulation degradation in cases of motor lock, motor lead short circuit, overload, over voltage, and/or other failure. Please add the protection circuit to your product.**
- 3.There is no reverse-connection prevention diode of VDC (+) and GND (-) installed in this product. Therefore, if VDC(+) and GND(-) are reverse connected, it may cause smoking, ignition, and/or destruction, although these conditions may not manifest immediately. We recommend that a protection device be installed on your product when there is a possibility of reverse-connection.**
- 4.Please verify that this product is being installed and used in compliance with all safety standards. Please inform SUNON of any safety concerns prior to releasing your product to production.**
- 5.Please handle and install this product carefully. Hitting or dropping this product may cause damage.**
- 6.Please do not damage this product including coil and lead wires while installing or wiring. There may be smoking or fire.**

建準電機工業股份有限公司 SUNONWEALTH ELECTRIC MACHINE INDUSTRY CO., LTD.	SPEC.NO	D04041840G-00	REVISION DATE	06. 29. 2005
	ISSUE DATE	06. 02. 2005	E D I T I O N	研 發 部
	P A G E	6 O F 9		94.07.11



Notes

II . Specification modification

- 1.SUNON offers engineering assistance on fan installation and cooling system design.

- 2.Any change to the parameters specified in this document will be determined by mutual agreement between both parties. Parameters which are not specified in this specification will be identical to the final sample which has been approved by your company.

- 3.Product will be shipped in accordance with this specification unless Sunon has been previously notified of parameters requiring exception.

- 4.Parameters modified by mutual consent will be incorporated in this specification.

- 5.Please notify SUNON in advance of any modification to your product or new application for this fan which may require a review of this specification.

建準電機工業股份有限公司 SUNONWEALTH ELECTRIC MACHINE INDUSTRY CO., LTD.	SPEC.NO	D04041840G-00	REVISION DATE	06. 29. 2005
	ISSUE DATE	06. 02. 2005	E D I T I O N	研 發 部
	P A G E	7 O F 9		94.07.11



Notes

III . Other

1. When building your device, please examine thoroughly any variation of EMC, temperature rise, life data, quality, etc. of this product by shock/drop/vibration testing, etc. If there are any problems or accidents in connection with this product, it should be mutually discussed and examined.
2. Fan holders or bearings may be damaged if touched with fingers or other objects. Additionally, static electricity (ESD) may damage the internal circuits. Please handle this product carefully.
3. Please avoid operating SUNON's product in poisonous material (organic silicon, cyanogens, formalin, phenol, etc.) or corrosive gas environments (H2S, SO2, NO2, Cl2, etc).
4. SUNON does not warrant performance safety against accidents caused by dust, water, droplets, dew, bugs, etc.
5. Please advise us in advance if you require documents for export.
6. Improper mounting may cause harsh resonance, vibration, and noise. Please mount securely.
7. Safety is a top priority. Please furnish guard accessories to prevent injury to personnel.
8. Unless otherwise noted, all tests are conducted at 25°C ambient temperature and 65% relative humidity.
9. Always ensure that fans are stored according to the storage temperatures specified. Do not store in a high humidity environment. If the fans are stored for more than 6 months, SUNON recommends functional testing before using.
10. SUNON reserves the right to use components with equivalent specifications from multiple sources.

建準電機工業股份有限公司 SUNONWEALTH ELECTRIC MACHINE INDUSTRY CO., LTD.	SPEC.NO	D04041840G-00	REVISION DATE	06. 29. 2005
	ISSUE DATE	06. 02. 2005	E D I T I O N	開發部
	P A G E	8 O F 9		94.07.11



Declaration of RoHS

Control declaration of environment- related substances/ materials

1. In accordance with the Restriction of Hazardous Substances (RoHS) Directive, Sunon product with P/N: GN models have complied with law and discipline not to employ the forbidden substances, and restrict the allowable concentration of some limited substances deliberately in our components.

No	Substance	Criteria
1	Halogens & its compounds (Substances depleting the ozone layer)	Forbidden
2	Chlorinated Organic Solvent	Forbidden
3	Plastic (Frame, Impeller, wire harness, etc.)	< 100ppm
	Solder	< 1000ppm
	Iron Alloy	< 3500ppm
	Aluminium Alloy	< 4000ppm
	Copper Alloy	< 4wt%
4	Solder	< 20ppm
	Cadmium Alloy	< 100ppm
	Plastic	< 5ppm
5	PBB and PBDE Category	Forbidden
6	PCB and PCT Category	Forbidden
7	CP	Forbidden
8	Mirex	Forbidden
9	PCN category	Forbidden
10	Hexavalent Chromium Compounds	< 100ppm
11	Mercury and its compounds	Forbidden
12	Asbestos	Forbidden
13	Organic Tin Compounds	Forbidden
14	Azo Compounds	Forbidden